Project Hash

CHECKLIST

New miner setup checklist

From unboxing to the first hour of hashing.

BEFORE POWER-ON

- [ ] Check the box and the unit for transport damage.
- [ ] Photograph the serial label and keep the invoice.
- [ ] Confirm the circuit matches the voltage and power on the rating label.
- [ ] Plan airflow so hot exhaust cannot reach the intake.
- [ ] Keep the spot dry and free of dust.

FIRST START

- [ ] Connect the network cable, then the power.
- [ ] Find the miner's IP address in your router or the maker's IP tool.
- [ ] Change the default dashboard password.
- [ ] Enter your pool address, worker name and password.

FIRST HOUR

- [ ] Compare the hashrate with the rated figure.
- [ ] Check every board reports and temperatures look even.
- [ ] Check every fan spins and none is noisy.
- [ ] Note the date, settings and readings in a log.

NOTES

General guidance. Where your maker's manual or terms differ, follow them.